

BEAM REINFORCEMENT SCHEDULE FOR GROUND FLOOR - GROUND BEAMS											
BEAM (MARK)	BOTTOM REINFORCEMENT		TOP REINFORCEMENT			LINKS			SIDE BARS EACH FACE	LINK ARRANGEMENT	REMARKS
	B1	B2	TOP-LEFT	TOP-MID	TOP-RIGHT	LINKS-LEFT	LINKS-MID	LINKS-RIGHT			
GB1	2T16	2T16	2T16+2T16	2T16+2T16	2T16+2T16	2L-T10@200	2L-T10@200	2L-T10@200	2T12		REFER TO S-300 DETAILS T1 & T2
GB2	2T16	2T16	2T16+2T16	2T16+2T16	2T16+2T16	2L-T10@250	2L-T10@250	2L-T10@250	2T12		REFER TO S-300 DETAILS T1 & T3
GB3	2T16	--	2T16+2T16	2T16	2T16	2L-T10@150	2L-T10@150	2L-T10@150	2T12		REFER TO S-300 DETAILS T1 & T3
GB4	2T16	--	2T16+2T16	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		REFER TO S-300 DETAILS T1 & T2
GB5	2T16	--	2T16+2T16	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		REFER TO S-300 DETAILS T1 & T2
GB6	2T16	--	2T16+2T16	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		REFER TO S-300 DETAIL T1 & T4 & T5
GB7	2T16	--	2T16+2T16	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		REFER TO S-300 DETAIL T1 & T4

BEAM REINFORCEMENT SCHEDULE FOR FIRST FLOOR - MAIN VILLA											
BEAM (MARK)	BOTTOM REINFORCEMENT		TOP REINFORCEMENT			LINKS			SIDE BARS EACH FACE	LINK ARRANGEMENT	REMARKS
	B1	B2	TOP-LEFT	TOP-MID	TOP-RIGHT	LINKS-LEFT	LINKS-MID	LINKS-RIGHT			
FB1	3T16	--	--	--	3T16+2T20	--	--	2L-T10@150	--		CANTILEVER BEAM
FB2	2T20	2T20	SEE ADJ. BEAM	3T16	3T16+2T20	2L-T10@100	2L-T10@150	2L-T10@100	2T12		
FB3	2T16	2T16	SEE ADJ. BEAM	3T16	3T16+2T16	2L-T10@150	2L-T10@150	2L-T10@100	2T12		
FB4	3T16	--	SEE ADJ. BEAM	3T16	3T20+3T20	2L-T10@150	2L-T10@150	2L-T12@150	2T12		
FB5	3T16	--	SEE ADJ. BEAM	--	--	2L-T12@150	--	--	2T12		CANTILEVER BEAM REFER TO S-300 DETAIL T8
FB6	2T16	2T16	3T16	3T16	3T16	2L-T10@150	2L-T10@150	2L-T10@150	2T12		
FB7	3T16	--	3T16+2T16	2T16	3T16+2T16	2L-T10@100	2L-T10@150	2L-T10@150	--		CANTILEVER BEAM
FB8	3T16	--	3T16	3T16	3T16+2T20	2L-T10@150	2L-T10@150	2L-T12@150	--		CANTILEVER BEAM
FB9	2T16	2T16	3T16	2T16	3T20+3T20	2L-T10@150	2L-T10@150	2L-T12@150	--		CANTILEVER BEAM
FB10	3T16	--	--	--	3T16+2T16	--	--	2L-T12@150	--		CANTILEVER BEAM
FB11	3T16	--	SEE ADJ. BEAM	3T16	2T16+2T16	2L-T12@150	2L-T10@150	2L-T12@150	2T12		
FB12	3T16	--	SEE ADJ. BEAM	2T16	3T16+2T16	2L-T12@150	2L-T10@150	2L-T10@150	2T12		
FB13	3T16	--	2T12	2T12+2T12	3T16+2T12	2L-T10@150	2L-T10@150	2L-T10@150	--		
FB14	2T16	--	2T12	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	--		
FB15	2T16	2T16	2T12	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		
FB16	3T16	--	2T12+3T16	2T12	3T16+2T16	2L-T12@100	2L-T10@150	2L-T12@150	2T12		
FB17	3T16	--	SEE ADJ. BEAM	3T16	2T16	2L-T10@150	2L-T10@150	2L-T10@150	2T12		
FB18	3T16	--	--	--	2T12	--	--	2L-T12@150	2T12		CANTILEVER BEAM REFER TO S-300 DETAIL T11
FB19	3T16	--	3T16	--	--	2L-T10@150	--	--	2T12		CANTILEVER BEAM REFER TO S-300 DETAIL T11
FB20	3T20	--	2T20+2T20	2T20	3T20	2L-T12@100	2L-T10@150	2L-T12@150	2T12		DOUBLE CANTILEVER BEAM
FB21	2T16	--	2T16	2T16	2T16	2L-T10@150	2L-T10@150	2L-T10@150	--		
FB22	12T16	--	12T16	12T16	12T16+10T16	6L-T10@150	6L-T10@150	6L-T10@150	--		
FB23	12T20	--	SEE ADJ. BEAM	12T16	12T16+8T16	6L-T10@200	6L-T10@200	6L-T10@200	--		
FB24	12T16	--	SEE ADJ. BEAM	12T16	12T16	6L-T10@200	6L-T10@200	6L-T10@200	--		
FB25	2T16	2T16	2T16+2T16	12T16	12T16+2T16	2L-T10@150	2L-T10@150	2L-T10@150	--		
FB26	12T20	10T20	12T16	12T16	10T16	6L-T12@150	6L-T12@150	6L-T12@150	--		TRANSFER BEAM REFER TO S-301 DETAILS F1 & F2
FB27	10T20	10T20	10T16	10T16	10T16	6L-T12@150	6L-T12@150	6L-T12@150	--		TRANSFER BEAM

BEAM REINFORCEMENT SCHEDULE FOR FIRST FLOOR - GARAGE											
BEAM (MARK)	BOTTOM REINFORCEMENT		TOP REINFORCEMENT			LINKS			SIDE BARS EACH FACE	LINK ARRANGEMENT	REMARKS
	B1	B2	TOP-LEFT	TOP-MID	TOP-RIGHT	LINKS-LEFT	LINKS-MID	LINKS-RIGHT			
G-FB1	3T20	2T20	2T20+2T20	2T20	2T20+2T20	2L-T12@150	2L-T10@150	2L-T12@150	--		PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
G-FB2	3T16	--	2T16	2T16	2T16+2T16	2L-T10@150	2L-T10@150	2L-T10@100	--		
G-FB3	3T16	--	SEE ADJ. BEAM	2T16	2T16	2L-T10@100	2L-T10@150	2L-T10@150	--		INVERTED BEAM
G-FB4	2T16	2T16	2T16+2T16	2T16	3T16	2L-T10@100	2L-T10@150	2L-T10@150	--		INVERTED BEAM

BEAM REINFORCEMENT SCHEDULE FOR ROOF FLOOR											
BEAM (MARK)	BOTTOM REINFORCEMENT		TOP REINFORCEMENT			LINKS			SIDE BARS EACH FACE	LINK ARRANGEMENT	REMARKS
	B1	B2	TOP-LEFT	TOP-MID	TOP-RIGHT	LINKS-LEFT	LINKS-MID	LINKS-RIGHT			
RB1	2T16	2T16	3T16	2T16	3T16	2L-T10@150	2L-T10@150	2L-T10@150	2T12		CANTILEVER PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB2	2T16	2T16	SEE ADJ. BEAM	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB3	2T16	2T16	SEE ADJ. BEAM	2T12	2T12+2T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB4	2T16	2T16	SEE ADJ. BEAM	2T12	2T12+3T16	2L-T10@150	2L-T10@150	2L-T10@150	2T12		CANTILEVER PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB5	2T16	2T16	2T20+2T20	2T20+2T16	2T20	2L-T10@150	2L-T10@150	2L-T10@150	2T12		CANTILEVER BEAM
RB6	2T16	2T16	SEE ADJ. BEAM	2T12	3T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		
RB7	2T16	2T16	2T12+2T16	2T12	2T12+3T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		CANTILEVER PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB8	2T16	2T16	SEE ADJ. BEAM	3T12	3T12	2L-T10@150	2L-T10@150	2L-T10@150	2T16		PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB9	2T16	2T16	SEE ADJ. BEAM	2T12	2T12+3T12	2L-T10@150	2L-T10@150	2L-T10@150	2T12		PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB10	2T16	--	SEE ADJ. BEAM	3T12	3T12+3T16	2L-T10@150	2L-T10@150	2L-T10@100	2T12		CANTILEVER PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB11	2T16	2T16	3T12+3T20	3T12	3T12+3T16	2L-T10@100	2L-T10@150	2L-T10@150	2T12		CANTILEVER PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB12	2T16	2T16	SEE ADJ. BEAM	3T12+3T16	3T12+3T16	2L-T10@100	2L-T10@150	2L-T10@150	2T12		CANTILEVER PARTIALLY INV. BEAM REFER TO PLAN FOR TOB LEVEL
RB13	3T16	--	3T16	--	--	2L-T12@150	--	--	2T12		CANTILEVER BEAM REFER TO S-300 DETAIL T11
RB14	3T20	--	2T16+2T16	2T16	3T16+3T16	2L-T12@100	2L-T10@150	2L-T12@100	2T12		DOUBLE CANTILEVER BEAM
RB15	4T16	--	--	--	4T20	--	--	2L-T12@100	2T12		CANTILEVER BEAM REFER TO S-300 DETAIL T11
RB16	2T16	--	3T16	3T16	3T16	2L-T10@200	2L-T10@200	2L-T10@200	--		
RB17	13T16	--	10T16	10T16+5T16	10T16+12T20	6L-T10@200	6L-T10@200	6L-T10@200	--		
RB18	12T20	--	SEE ADJ. BEAM	10T16	10T16+12T20	6L-T10@200	6L-T10@200	6L-T10@200	--		
RB19	12T16	--	SEE ADJ. BEAM	10T16+5T16	10T16	6L-T10@200	6L-T10@200	6L-T10@200	--		

BEAM REINFORCEMENT SCHEDULE FOR UPPER ROOF FLOOR											
BEAM (MARK)	BOTTOM REINFORCEMENT		TOP REINFORCEMENT			LINKS			SIDE BARS EACH FACE	LINK ARRANGEMENT	REMARKS
	B1	B2	TOP-LEFT	TOP-MID	TOP-RIGHT	LINKS-LEFT	LINKS-MID	LINKS-RIGHT			
URB1	3T16	--	3T16	3T16	3T16+3T16	2L-T10@150	2L-T10@150	2L-T10@150	--		
URB2	3T16	--	SEE ADJ. BEAM	2T16	3T16+2T16	2L-T12@100	2L-T10@150	2L-T12@100	2T16		
URB3	2T16	2T16	SEE ADJ. BEAM	3T16	3T16	2L-T10@150	2L-T10@150	2L-T10@150	--		
URB4	2T16	2T16	3T16	2T16	3T16	2L-T10@100	2L-T10@150	2L-T10@150	--		CANTILEVER BEAM
URB5	2T16	2T16	2T16+2T16	2T16+2T16	2T16+2T16	2L-T12@150	2L-T10@150	2L-T10@150	--		
URB6	3T20	2T16	SEE ADJ. BEAM	3T16	3T16+3T16	2L-T10@150	2L-T10@150	2L-T10@150	--		
URB7	2T16	2T16	SEE ADJ. BEAM	3T16+3T16	3T16+3T16	2L-T10@150	2L-T10@150	2L-T10@150	--		
URB8	2T16	2T16	SEE ADJ. BEAM	3T16	3T16	2L-T12@150	2L-T10@150	2L-T10@150	--		
URB9	2T16	--	2T12	2T12	2T12	2L-T10@150	2L-T10@150	2L-T10@150	--		
URB10	2T20	2T20	3T16+3T12	3T16	3T16	2L-T12@100	2L-T10@150	2L-T10@150	--		
URB11	3T20	--	3T16	2T16	3T16	2L-T12@200	2L-T10@150	2L-T12@200	--		

- GENERAL NOTES
1. This Drawing Issue has been checked and approved in accordance with the LOCI Quality Management System.
 2. All works shall be carried out in accordance with particular & general specifications, in conjunction with relevant conditions of contract.
 3. This drawing shall not be used directly for Construction, but for preparation of Shop Drawings in coordination with other disciplines and Suppliers prior to manufacture, delivery and execution on site.
 4. All dimensions and levels are in millimeter, unless noted otherwise. Only written dimensions to be followed and not scaled from the drawing.
 5. All dimensions to be verified at site and coordinated with other disciplines' manufacturers in the preparation of shop drawings. Any changes shall be validated by the consultant.
 6. For elements with indicative design, the contractor / supplier shall submit complete construction details and technical specifications for approval prior to execution. Shop drawings to particularly incorporate details at structural expansion joints as well as expansion / construction joints needed for the respective materials/ finishes / related works.
 7. Safety standards and statutory regulations shall be adhered to in the manufacture, supply, storage and installation of all works.
 8. Any discrepancy or ambiguity whatsoever with dimensions / details / legends / specifications / etc, shall be brought to the attention of the Consultant and clarification obtained prior to finalization of tender / construction.

DRAWING REVISIONS			
REV	DATE	DESCRIPTION	CHECKED APPROVED
00	14.03.2025	ISSUED FOR APPROVAL	AN BR

CLIENT

TARUN HARISH CHANDRA KHANNA

DRAWING DETAILS

BEAMS SCHEDULE

SHEET #

269-S-200

REVISION	ISSUE DATE:	SCALE @ A1
R0	14-03-2025	AS SHOWN



PROJECT LOCATION

PLOT NO. 3630160

Al Manara, Dubai

PROJECT NUMBER

269

PROJECT PHASE

DETAIL DESIGN

CONSULTANT

LOCI

لوکار

Office M31, KIA Flagship Building
Sheikh Zayed Rd, Al Quoz 1
P. O. Box 72928, Dubai

T +971 4 357 6573
W www.loci.ae